



सत्यमेव जयते

प्रसार भारती

(भारत का लोक सेवा प्रसारक)

कार्यालय अपर महानिदेशक अभि. (उ.क्षे.)

आकाशवाणी एवं दूरदर्शन

8 वां तल सूचना भवन, सी0जी0ओ0 काम्पलेक्स
नई दिल्ली110003



सत्यम् शिवम् सुन्दरम्

Tender No. ADG(NZ)/TVP/23-24/Snow Shade and Step Fabrication at HPT Patnitop(Nathatop)

Date: 19.03.2024

Subject: Snow Shade and Step Fabrication at HPT Patnitop (Nathatop).

1. The budgetary quotation of the upcoming tender is enclosed herewith to offer comments, if any by prospective bidders/firms.
2. Bidders/firms are requested to provide information about content in respect of works along with budgetary quote.
3. Bidders/firms may please submit the above detail on or before due date by e-mail totvstudio70@gmail.com or at following Address.

Room No.899-D
O/o ADG(E-NZ)
Akashwani & Doordarshan,
8th floor, CGO Complex,
Soochna Bhawan, New Delhi-110003.

Budgetary Quotation for: Snow Shade and Step Fabrication at HPT Patnitop (Nathatop).

Due Date to offer Comments: 26.03.2024

Enclosed:

1. Budgetary Quotation form of the upcoming tender is enclosed herewith to offer comments, if any by prospective bidders/firms.

(Shyam Sunder)
Engineering Assistant
for Addl. Director (E)(NZ)



सत्यमेव जयते

प्रसार भारती

(भारत का लोक सेवा प्रसारक)

कार्यालय अपर महानिदेशक अभि. (उ.क्षे.)

आकाशवाणी एवं दूरदर्शन

8 वां तल सूचना भवन, सी0जी0ओ0 काम्पलेक्स

नई दिल्ली-110003



Tender No. ADG(NZ)/TVP/23-24/Snow Shade and Step Fabrication at HPT Patnitop(Nathatop) Date: 19.03.2024

M/s.

Subject: Snow Shade and Step Fabrication at HPT Patnitop (Nathatop).

Dear Sir,


Some works are required to be done at HPT Patnitop as per subject.

On behalf of the Prasar Bharati (I.P.S.B.), online tenders are to be invited by this Organization in the prescribed Bid Forms. Before the tender process the estimation of the work is to be done. Please furnish your budgetary quote for the stores/works mentioned below.

Sl No.	Description/Characteristics of items & work	Qty	Rate	Amount
1.	Fabrication and Installation of Snow/rain/wind/sun shade measuring 35'(L)x5.6'(W) approx. extending between external ceiling surface outside Heat ex-changer room & main Transmitter hall at ground floor includes; Scope of works 1. Fabrication of Square MS grid structure measuring 35' (L) x 5.6'(W) so as to cover existing ladder structure extending between external ceiling surface outside Heat ex-changer room & main Transmitter hall at ground floor. 2. Entire MS super structure shall be fabricated out of Apollo or equivalent Square MS pipes of min.2mm thickness. 3. All such MS pipes shall be professionally welded at regular intervals, with an additional centre MS pipe member running along entire 35' length as per directions of officer-in-charge/IO at site. 4. The MS Structure so prepared will be subsequently welded above the staircase at suitable height, with existing MS poles at regular intervals i.e. both ends of staircase structure, mid- way of staircase structure at intermediate points so as to provide sufficient anchor and support as per directions of officer-in-charge /IO at site in such a way that overall structure does not succumb to heavy snow fall in winter, thunder storms, rain and high speed wind currents of mountains.	1 Job Complete		
2.	Galvanized Sheet Work: Entire MS structure including central rib after welding work shall be finally covered with superior quality Galvanized Iron /metro sheets. All the Galvanized/metro sheets work shall be firmly fixed with super structure members by means of 2 1/2" Steel screws at regular intervals.	1 Job Complete		
3.	Scaffolding Material: - Charging towards hiring of Scaffold Material.	1 Job Complete		
4.	Step Fabrication: - GI Chequered platform stairs steps are to be welded to the already laid basic structure of 16 steps so as to enable a proper foot hold of feet on the stair heaving dimension of GI Chequered plate (813mm x 254mmX 8mm each (W XL) and welded in a very professional way not to leave any brazing unattended.	1 Job Complete		

5.	Snow & Rain stairs protection:-Snow & Rain stairs protection since the area is mountains & the are exposed to snow, rain a high-speed wind and during winter accumulation of snow on stairs & for the purpose of safety of man& machinery side protection from one side of the entire stair is to be fabricated & welded of MS square pipe total length measuring 38' (Approx) in length in polycarbonate sheet to the entire exposed side opposite L shape & heaving .7' of height of MS structure 50mmx50mmx6mm MS square pipe and 8-10mm polycarbonate sheet. This rectangular type grid structure of fabrication is to be welded to the stair & side wall sport in a way so that it can stand the fury wind of mountains.	1 Job Complete		
6.	Stairs rallying sport for men: - Stairs leading from Transmitter Hall leading to Heat exchanger room consisting of 20steps having only one side railing is to be reinforced by providing a full length 2"GI pipe round 20' length from other side (wall side) from step one to upper platform is to be welded and support to be given at the interval of 4 feet, so as to provide full support to the railing and stair as well.	1 Job Complete		
7.	Enamel paint work for above Snow/rain/wind/sun shade: a. All the metallic members of fabricated shade work including super structure, ribs, anchoring plates, nuts and bolts. screws etc. shall be primarily painted with two coats superior quality branded primer/red oxide followed by 2 to 3 coats of ISI marked superior quality branded enamel paint (similar to Asian/Nerolac etc. Colour will be decided by Officer-in-charge /IO at site. b. Enamel paint work for Step Fabrication Snow & Rain stairs protection: -All the members of fabricated structure workincluding super structure, ribs, anchoring plates, nuts and bolts etc shall be primarily painted with two coats superior quality branded primer/red oxide followed by 2 to 3 coats of ISI marked superior quality branded enamel paint (similar to Asian/Nerolac etc. Colour will be decided by Officer-in-charge /IO at site.	1 Job Complete		
8.	Fabrication providing and fixing of MS Ventilation grill of size 4'x3'. Scope of work:- 1. Removing of old 2 nos Glass partition of size 4'x3' from its position and stacking of useful material at safe place decided by IO at site. 2. Plastering all damage corners by cement sand ratio 1:6. 3. Providing and fixing MS ventilation grill of size 4'x3' with MS frame and suitable quantity of MS blinds. Job include priming and painting of grill.	1 Job Complete		
	Note:- (i) Job includes labour and all hidden charges at site. (ii) The site is approximately 60 kilometer from the Udampur on hilly terrain.			
	SubTotal			
	GST			
	Total			

The budgetary quote may be submitted within Seven days.


 (Shyam Sunder)
 Engineering Assistant
 for Addl. Director General (E)(NZ)